

EAST COAST RAILWAY

FAX: 0674-2302524  
:50740 (Railway)

Office of the  
Principal Chief Electrical Engineer,  
3<sup>rd</sup> Floor, South Block,  
Rail Sadan, C.S.Pur,  
Bhubaneswar -751017

No: ECoR/EL/G/452/07/Cable Laying/ 199

Dated 25.01.2018

Sr.DEE (G)/KUR,WAT,SBP

Sub: Laying of Cables in concrete surface/under track by Electrical Deptt.

Ref: Minutes of works review meeting held on 10.01.2018.

The following instructions are to be implemented for laying of cables in already concreted surface/under Rly track by Electrical department through contractual agency for all works.

1. In concreted area like concrete platforms, road crossings and at places where it is not possible to lay cable at a minimum depth of 1mtr due to concrete structure coming on the cable route, the cable laying has to be done through micro drilling.

2. To avoid damage to existing formation, track crossing for laying of cable to be done through micro drilling.

3. Provision of laying of cables through micro drilling has to be kept in the tender schedule for all future works as per requirement and feasibility.

4. For the ongoing works, where provision for laying of cables through micro drilling is not available, the same is to be done through operation of NS item or through separate tender/quotations.



(Sandip Roy)

Chief Electrical Services Engineer

Copy to: CEE/Con/BBS, CPD/RE/BBS, GGM (Elect/RVNL) :-For kind information and necessary action pls.