

East Coast RailwayEngineering Department

Office of the Chief Engineer,  
B-79, Rail Vihar, CSP,  
Bhubaneswar – 751 023.

CE's CIRCULAR No.12Sub: ACCOUNTAL OF SEJs & GLUED JOINTS

The following procedures shall be followed for keeping the details of SEJs / Glued joints:

- 1) On web of rail (out side) the detail of SEJ shall be painted with yellow paint as A, B, C, D, E & F which are:

A = Firm's Code As given in Annexure I & II. In case of any addition / deletion of supplier same to be updated as and when required.  
B = Month when supplied  
C = Year when supplied  
D = Track Depot – Code – Cuttack=CTC, Waltair=WAT, Sambalpur=SBP  
E = Month of laying  
F = Year of laying

- 2) After receipt of supply from firm OS (Track Depot) / SSE (P-Way) shall paint following with yellow paint on web portion of rail.

A = Firms Code  
B = Month when supplied  
C = Year when supplied  
D = Track Depot – Code – Cuttack=CTC, Waltair=WAT, Sambalpur=SBP

- 3) OS (Track Depot) / Sectional SSE (P-Way) shall maintain a register with following details:

Sl. No.	Details of receipt of materials						Issue details			
	Item	Drawing No.	PO No.	Name of firm which supplied	Quantity	Date of Receipt	Date	Issued		Issue note no. **
								Consi- gnee	Qty.	
1	2	3	4	5	6	7	8	9	10	11

\*\* Issue note numbering to be given as - OS Track Depot/Code/1,2,3 etc.

o/c

4) While issuing the material OS (Track Depot) / SSE(P) will give following details to consignee:-

Sl. No.	Issue Details							
	Item	Drawing No.	PO No.	Name of firm which supplied	Date of Issue	Qty.	Consignee	Issue Note No. of Track Depot
1	2	3	4	5	6	7	8	9

5) Sectional SSE (P-Way) shall maintain a register with following details after receipt of SEJ / Glued joints from OS (Track Depot):

Sl. No.	Receipt Detail						Laying Details				
	Item	Drg. No.	Name of firm which supplied	Issue Note No. of Track Depot who issued	Date of Receipt	Qty.	Location where laid	Date of laying	Defects found if any during time of laying	Details of failure	
1	2	3	4	5	6	7	8	9	10	11	

6) SSE/P-Way will paint E&F (as indicated in Para 1 above) on the web of the rail i.e.

E = Month of laying

F = Year of laying

The typical example – CS / 03 / 04 / CTC / 04 / 04

7) Above instructions should be followed with immediate effect. In case of SEJs / Glued joints already available with SSE / P-Way, complete details should be painted by them.

  
( J.S. Tolia ) 3/9/04

Chief Track Engineer

No.W-2/118/CE/Circular (Works)/Pt.I 0737

Dt. September 3, 2004

*Distribution:*

1. Divisional Railway Manager, KUR, SBP & WAT
2. CAO / C / BBS
3. CTE, CGE & CBE / BBS
4. CWM / MCS
5. Sr. DEN (Co.) / KUR / SBP / WAT
6. Dy. CE (Track / TP / G / Br.) / BBS
7. OS Track Depot of KUR / SBP / WAT

**APPROVED VENDORS OF IRS DESIGN OF SWITCH EXPANSION JOINT**

*Effective from 01.07.2004 to 31.12.2004*

**PART-I**

**Annexure-I**

<b>Sr. No.</b>	<b>Name of Firm</b>	<b>Firm's Code</b>
1	B. Chandra Bose Engineering Contractor, 36/144, Thangamapuri Pattinam, Salem Distt., Mettur Dam-636 402 (TN)	BC
2	Bina Metal Way Ltd., B-4, Phase-II Industrial Area, Adityapur, Jamshedpur-83 1013 (Jharkhand)	BM-I
3	Bina Metal Way Ltd., 620, URLA Industrial Area, URLA Raipur (C.G.)	BM-II
4	Calcutta Springs Ltd., 18, R.N. Mukherjee Road, Kolkata-700 001	CS
5	Castle Industries Pvt. Ltd., Kalyani Industrial Estate, Shed No.14 Kalyani Nadia (W.B.)	C-1
6	Cemcon Track Industries, 8 Km Stone, Panipat Road, Near Mudlana Village, Gohana (Haryana)	CT
7	Chinttpurni Engg. Works, Jahangirabad Road, Barabanki-225 123 (UP)	CH
8	Digvijay Steels Pvt. Ltd., GT Road, Batala-143505 (Punjab)	DS
9	J. Sons Engineering Corp Ltd., J. Sons House, Garh Road, Meerut-250002 (UP)	JE
10	J.S. Industries Pvt. Ltd., Plot No.145A, Industrial Development Area, Bollaram Village, Medak Distt.-502325 (AP)	JS
11	Paramount Enterprises, 4-1-889/16/3, Tilak Road, Hyderabad-500001	PE
12	Rahee Industries Ltd., Century Towers, 5 <sup>th</sup> Floor, 45 Shakespeare Saran, Kolkata-700 017	RI
13	Sandhu Technocrats Pvt. Ltd., Jawahar Nagar, Mando Jamshedpur-832110 (Jharkhand)	ST
14	Shalimar Fastening Pvt. Ltd., Century Towers, 5 <sup>th</sup> Floor, 45, Shakespeare Sarani, Kolkata-700 017	SF
15	Swastika Spokes Manufacturing Co., 5/15Gujarat Industrial Township, Phase-I, VATVA, Ahmedabad-382445	SW

**APPROVED VENDORS OF GLUED INSULATED RAIL JOINTS**

*Effective from 01.07.2004 to 31.12.2004*

**PART-I**

**Annexure – II**

Sr. No.	Name of Firm	Firm's Code
1	Arvind Industries, 4, BBD Bag (E), III floor, Room No.51-C Kolkata-700001	AR
2	Chinttpurni Engg. Works H.O. B-6, Sector B, Aliganj Lucknow-226024 (UP)	CH
3	Creative Engineers Kalpana Mala Road, Near Agarwal Nursing Home, Kota-324002	CR
4	Dynamic Engineers Plot No.E-20, Industrial Area, Opp. Multi Metal, Kota	DE
5	Eastern Udyog 41, NS Road, 4 <sup>th</sup> floor, Room No.406, Kolkata-700001	EU
6	Eden Vinimay Pvt. Ltd., 22, Strand Road, Ground Floor, Kolkata-700 001	EV
7	Kotson Engg. Corp., 18-12-16, Andhra Ratna Road, Tenali-522201 (AP)	KT
8	Kushal Engg. Co., 59, Mumbai Samachar Marg, Sonawala Bldg., 1 <sup>st</sup> Floor, Mumbai-400 023	KE
9	Paramount Enterprises, 4-1-889/16/3, Tilak Road, Hyderabad	PE
10	Shanti Udyog, B-22 & 24, Phase-I, Adityapur Industrial Area, Jamshedpur-832109 (Jharkhand)	SU
11	Shyama Shyama Glue Tech Opp. Sudhir Dharam Kanta, Mathura Road, Sikandara, Agra-282007 (UP)	SS
12	The India Thermit Corporation Ltd., 84/22, Fazalganj, Kanpur-208012	IT

**PART-II**

1	Calcutta Springs Ltd., 18, RN Mukherjee Road, Kolkata-700001	CS
2	Ganapati Industrial Pvt. Ltd., 2, Hare Street, Nicco House, 6 <sup>th</sup> Floor, Kolkata-700 001	

PART-II

1	Ganapati Industrial Pvt. Ltd., 2, Hare Street (Nicco House), VI Floor, Kolkata-700 001	GI
2	Hindustan Engineering & Industries Ltd., Mody Building, 27, Sir R.N. Mukherjee Road, Kolkata-700 001	HE
3	N. Mohanlala & Co., 4 <sup>th</sup> Lane, Darukhana, Mumbai-400 010	NM
4	R.V. Industries, 23-A, Netaji Subhash Road, 11 <sup>th</sup> Floor, Room No.29, Kolkata-700 001	RV
5	Veekayan Industries Pvt. Ltd., G.T. Road, Batala-143505 (Punjab)	VI
6	Veerá Techno Trec Pvt. Ltd., Manimala, K-41, Hauz Khas Enclave, New Delhi-110 016	